No.	Items of work	Unit	Rate	Quantity	Rates to be quoted
			Rs. a. p.		
14	Roofing details as above span 7½′ ..	Sqr.	75 0 0	5·89	
15	Flooring with 9″ rough boulders and sand filling over that 3″ stone jelly concrete in lime mortar covered with 1½″ cement concrete mixed with approved colour, plaster finish including rounding off corners, etc., complete	,,	25 0 0	10·41	
16	Cornice with brick in mortar 9″ deep (as per drawing) including plastering, etc., complete	R.ft.	0 9 0	249	
17	Parapet wall ¾′ thick 2½′ high (as per drawing) brick in mortar including plastering colour washing, etc., complete ..	,,	1 8 0	237	
18	Plastering two coats of lime mortar (1 : 2) over brick wall	Sqr.	3 4 0	62·62	
19	Colour washing oustide, two coats ..	,,	0 5 0	31·31	
20	White washing inside, two coats	,,	0 4 0	31·31	
21	Painting teak wood doors and windows ..	,,	3 8 0	11·64	
22	Cement pointing with cut line in exposed faces of the basement	,,	3 8 0	3·23	
23	Top capital for the walls round the latrines with brick in mortar as per drawing ..	R.ft.	0 10 0	25	
24	Compound wall (including plastering colour washing) of brick in mortar with base and top as per drawing ¾′ thick and 5′ high	,,	2 4 0	41	
25	Building chimney to kitchen and bath ..	L.S.	50 0 0		

N. KRISHNA IYENGAR,
Executive Engineer.

MYSORE DIVISION.

Notification dated 4th April 1936.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Mysore Division, up to 2 P.M. on 20th April 1936, for Urgent Improvements to Malleswaraswamy's temple at Krishnarajpete. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1936.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Mysore, between the hours of 11 A.M. and 5 P.M. on office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees 170 in cash or Government Promissory Notes, as earnest money and be superscribed "Tender for Urgent Improvements to Malleswaraswamy's temple at Krishnarajpete," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, Mysore Division, Mysore, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office, in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Abstract estimate of quantities of urgent improvements to Malleswaraswamy's temple at Krishnarajpete.

No.	Items of work	Rate	Per	Quantity
	CONSTRUCTING COMPOUND WALL.	Rs. a. p.		
1	Dismantling and removing debris of old two houses as noted A and B in the plan	..	..	L. S.
2	Dismantling the front existing compound (as marked in the plan)	0 0 6	C.ft.	738
3	Constructing new compound	..		
	(*a*) Earthwork excavation for foundation ..	0 3 0	C.yd.	1
	(*b*) Filling foundation with chunam concrete ..	0 4 0	C.ft.	30
	(*c*) Size stone in mortar for foundation and basement	0 5 6	,,	97½
	(*d*) Ornamental coping in burnt brick in mortar ..	0 4 6	,,	12½
	(*e*) Kote thene ornamental above compound with masonry and plastering, etc., complete ..	1 8 0	R.ft.	10
	(*f*) Pointing with cement	3 0 0	Sqr.	1.50

N.B.—These quantities are for 10 feet length of compound; *196 feet compound wall is to be* constructed.

	II. CONSTRUCTING MAHADWARA AS PER PLAN.	Rs. a. p.		
1	Earthwork excavation for foundation	0 3 0	C.yd.	7
2	Filling in foundation with stone jelly chunam concrete	0 4 0	C.ft.	190
3	Size stone in chunam mortar	0 5 6	,,	832
4	Burnt stone slabs 6″ thick, neatly dressed and fixed ..	0 8 0	S.ft.	76
5	Burnt stone slabs 3″ to 4″ thick, neatly dressed and fixed on sand bed	40 0 0	Sqr.	3·69
6	Burnt stone posts and bases 1′ sqr. and 10′ high ..	1 0 0	C.ft.	58
7	Providing and fixing girders	13 0 0	Cwt.	16
8	Brick jelly concrete in quick lime (Kappi) beaten down over roofing slab	0 3 6	C.ft.	72
9	Cement pointing	3 0 0	Sqr.	12·26
10	Burnt brick in chunam cornice work including plastering as per plan	1 0 0	R.ft.	63
11	Ornamental mould work above roof for Basavanna as per sketch	..	..	L. S.
12	Ornamental wall in face of parapet	0 12 0	R.ft.	60
13	Coping over parapet including plastering	0 6 0	,,	60
14	Burnt stone brackets including dressing and fixing ..	2 0 0	Each	40
15	Providing teak wood door battened with ornamental floors fixed in the entrance with filling, etc., complete	1 12 0	S.ft.	96
16	Chocolate or slate colouring, two coats	3 8 0	Sqr.	1·92
	III. PROVIDING TERRACED PLATFORM.			
1	Earthwork required for levelling, etc.	..	..	L. S.
2	Masonry work required for steps	..	..	L. S.
3	Burnt stone slabs 6″ dressed and fixed	0 8 0	S.ft.	100
4	Providing a retaining wall in rough stone in mortar using old stones	0 2 0	C.ft.	265
5	Unforeseen charges found during execution ..	..	..	L. S.

Notification dated 4th April 1936.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Mysore Division, up to 2 P.M. on 27th April 1936, for Constructing a causeway with two vents at $\frac{3}{8}$ of T.Narasipur-Chamarajnagar road, across Mugur Addahalla and opening out a deviation road from 6/8 of T.Narasipur-Chamarajnagar road on to 4/2 of Mugur-Kollegal road. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of 193 .

2. The plans, detailed estimate and conditions may be seen at the Executive Engineers' Office at Mysore, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees 900 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for Constructing a causeway with two vents at $\frac{3}{8}$ of T.Narasipur-Chamarajnagar road, across Mugur Addahalla and opening out a deviation road from 6/8 of T.Narasipur-Chamarajnagar road on to 4/2 of Mugur-Kollegal road," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, Mysore Circle, Mysore, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office, in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for Contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Abstract estimate of opening out a Deviation Road from 6/8 of T.Narsipur-Chamarajanagar Road on to 4/2 of Mugur-Kollegal Road.

No.	Items of work	Per	Rate	Quantity	Cost
			Rs. a. p.		
1	Earthwork embankment forming road and consolidation, complete by stone road roller	C.yds.	0 4 0	6,193	
2	Collecting and stacking gravel for spreading on black cotton soil including $1\frac{3}{4}$ mile lead	,,	0 15 0	1,203	
3	Collecting and stacking sand to be mixed in proportion of $\frac{1}{2}$ to 1 with $\frac{1}{2}$ a mile lead	,,	0 5 0	602	
4	Spreading gravel and consolidating ..	,,	0 4 0	1,203	
5	Spreading sand	,,	0 2 0	602	
6	Collecting and stacking soling metal for the bed	,,	2 8 0	902	
7	Picking the gravel surface of road for spreading soling	S.yd.	0 0 $1\frac{1}{2}$	5,412	
8	Spreading and consolidation of soling metal	C.yd.	0 4 0	902	
9	Collecting and stacking broken metal to spread over soling	,,	3 0 0	451	

No.	Items of work	Per	Rate	Quantity	Cost
			Rs. a. p.		
10	Collection of gravel for spreading on soling and broken metal 20 C.yds. for each operation with $1\frac{3}{4}$ mile lead	C.yd.	0 15 0	320	
11	Spreading and consolidation of broken metal 20 C.yds. for each operation including $1\frac{3}{4}$ mile lead	,,	0 6 8	320	
12	Spreading and consolidation of broken metal	,,	0 6 8	451	
13	Spreading and consolidation of gravel ..	,,	0 3 9	320	
14	Providing and fixing mile stones	No	8 0 0	2	
15	Do Furlong stones ..	,,	2 8 0	7	
16	Constructing two vents	R.ft.	8 0 0	36	
17	Providing and fixing hand posts	Rds.	30 0 0	2	

Abstract estimate of constructing a Causeway with two vents at $\frac{3}{8}$ of T.Narsipur-Chamarajanagar Road across Mugur Addahalla.

1	Removing wet sand	C.yd.	0 2 0	1,800	
2	Earthwork excavation	,,	0 3 0	138	
3	Burnt stone jelly concrete in surki mortar	C.ft.	0 4 0	9,024	
4	Burnt size stone in surki mortar including through bond stones at every 6′ intervals in every course	,,	0 5 0	1,996	
5	Rough stone work with jelly paching between retaining walls road portions ..	C.yd.	2 0 0	830	
6	Filling boulders below apron with clay and jelly	,,	1 0 0	328	
7	Burnt stone slabs 6″ thick dressed and fixed in mortar	S.ft.	0 7 0	2,168	
8	Covering slabs over tunnel 9″ thick dressed and fixed in mortar	,,	0 10 0	280	
9	Clay paching below apron	C.yd.	0 10 0	189	
10	Baling out water putting ring bund, and etc.	L. S.	..	..	
11	Constructing wing walls by the sides of apron in front of tunnel vents ..	,,			

V. V. PATANKAR,
Executive Engineer.

ANJANAPUR DIVISION.

Abstract Notification dated 2nd April 1936.

Attention of the public is invited to the detailed Notification, published on pages 419 and 420, Part VI of the *Mysore Gazette*, dated the 26th March 1936, regarding the Auction Sale of certain Store Articles.

M. NARASIMHAIYA,
Executive Engineer.

KRISHNARAJSAGAR DIVISION.

Abstract Notification dated 30th March 1936.

The attention of the Public is invited to the detailed Notification published on pages 418 and 419, Part VI of the *Mysore Gazette*, dated the 26th March 1936, regarding the auction sale of two motors, *viz.*, one of 9 H.P. and the other of 20 H.P.

G. SESHAGIRI RAO,
Executive Engineer.